

Attachment I

Container Management Plan

**CONTAINER MANAGEMENT PLAN FOR THE POTENTIALLY LISTED 5100
CONTAINERS**

Inspections

The visible portions of the containers will be inspected weekly. Container surface areas will be inspected within the parameters of the current container storage array.

The containers will be inspected for rust over 75% of the surface area of the container, one or more concave dents of less than or equal to 30 degrees, visible leaks, and legible labeling reading "Hazardous Waste Pending Regulatory Determination."

Labeling

The containers will have labels reading "Hazardous Waste Pending Regulatory Determination."

Missing or illegible labels will be replaced or rewritten to ensure adequate marking.

Container Condition

Within two-hundred and seventy days (270) days of completion of the first inspection, DOE will repackage (i.e., over-packed or transferred to another container) containers that are identified by DOE during the first inspection under this Container Management Plan as: (1) being rusted over 75% of the surface area; (2) having one or more concave dents of less than or equal to 30 degrees; or (3) having visible leaks or penetration. In repackaging the containers, priority will be given to containers stored outside.

Within thirty (30) days of the relevant inspection, DOE will repackage (i.e., over-packed or transferred to another container) containers that are identified by DOE during subsequent inspections under this Container Management Plan as: (1) being rusted over 75% of the surface area; (2) having one or more concave dents of less than or equal to 30 degrees; or (3) having visible leaks.

Container Management

All containers will be placed on pallets or otherwise elevated to prevent contact with rainwater or a spilled material.

